

Jefferson County Community Ministries

202 Racetrack Street

Addendum #1

Insofar as the site improvements scheduled for 174 Racetrack Street have been delayed by JCCM, the site improvements work for 202 Racetrack Street need to be modified to provide utility services, as follows:

1. In accordance with the attached drawing C101, entitled "Site Plan for JCCM-174 Racetrack Street Building Renovation", prepared by Alpha Associates, Incorporated, dated 10/6/2023, the 8" PVC water line, Station 0+00 to 1+21 shall be constructed as part of this project. The 8" by 8" by 6" tee at Station 0+72, including 6' of 6" PVC service line and the 6" gate valve shall be installed. A 6" blind flange shall be installed on the gate valve for future extension and the end of the line shall be marked with an 8'- 2" by 4" wood post, painted blue. The 8" blind flange with a 2 " blowoff pipe at Station 1+21 shall be deleted from the plan.
2. Standard silt fence shall be installed along the length of the proposed 8" water line prior to starting the work.
3. The existing ditch along the street shall be regraded as needed after installation of the waterline.
4. Disturbed ground shall be seeded and mulched.